MYSORE DIVISION.

Notification dated 7th August 1936.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 2 P.M. on 31st August 1936, for Restoring Thuppadamadu Surankere, Register No. 1 of Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office, Mysore Division, between the hours of 11 A.M. and 5 P.M. on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Thuppadamadu Surankere, Register No. 1 of Nagamangala Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract of quantities for Restoring Thuppadamadu Surankere, Register No. 1 of Nagamangala Taluk.

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	BUND R. L. 55·00				
1	Cutting steps in bund and clearing jungle growth with roots, etc., and earthwork to pits of roots, etc	..	L. S.	..	50
2	Earthwork excavation for seat of bund and using the same for training bank including lead and lift, etc. ..	C.yd.	0 4 6	513	144
3	Earthwork to bund including lead of $\frac{1}{8}$ mile with watering and tamping ..	,,	0 4 0	6,555	1,844
4	Gravel backing to rough stone pitching including carting lead, etc.	,,	0 8 0	274	137
5	Rough stone pitching and consolidating, etc., with royalty complete . ..	,,	0 10 0	445	278
6	Turfing the slopes	Sqr.	0 10 0	454	284
7	Providing and fixing grade stones including engraving figures painting with bed slabs, etc., complete	Each.	2 0 0	17	34
8	Providing and fixing Index stones ..	,,	0 10 0	17	11
9	Do Bench mark stones ..	,,	4 0 0	2	8
10	Register No. and date stones	,,	4 0 0	1	4
11	Gauge stone	,,	20 0 0	1	20

Item No.	Description of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	II BREACH FILLING.				
1	Cutting steps and grips and removing boulders, etc., ...	..	..	L. S.	10
2	Cutting sand and silt and filling the same in rear of breach upto ground level and making platform at the rear toe of bund with watering and consolidation, complete	C.yd.	0 3 0	200	38
3	Puddle wall with mixture of gravel ..	,,	0 12 0	68	51
4	Gravel backing to revetment including lead, carting and consolidation ..	,,	0 8 0	27	13
5	Earthwork to breach including lead, carting, watering and tamping, etc., complete, including mixing of gravel in the proportion ordered ..	,,	0 6 0	583	219
6	New rough stone revetment including lead and lift, etc.	,,	1 10 0	53	86
7	Turfing	Sqr.	0 10 0	12·20	8
	CONSTRUCTING SLUICE AT R. L. 44·00				
1	Earthwork for cutting open the bund ..	C.yd.	0 3 0	74	14
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 6	162	46
3	Providing and fixing, C. I. pipes of 6″ diameter with 6″ fall, including lead joints, cutting pipes, threading, etc., complete, including earthwork ..	R.ft.	2 8 0	30	75
4	Size stone in surki mortar	C.ft.	0 5 0	464	145
5	Burnt stone slabs 6″ thick, dressed and fixed in mortar	S.ft.	0 8 0	84	42
6	Cement concrete slabs 1 : 2 : 4 ..	C.ft.	1 0 0	38	38
7	Cutting holes in guide and orifice slabs ..	Each.	1 0 0	3	3
8	Pointing with cement after raking joints	Sqr.	5 0 0	1·39	7
9	Providing and fixing jally wood plug and iron rod of 2″ diameter, including Locking arrangements, etc., complete ..	No.	20 0 0	1	20
10	Refilling the cut opened portion with watering and consolidation and forming, complete	C.yd.	0 3 0	39	7
	WASTE WEIR R. L. 50·00.				
1	Earthwork excavation and draft clearing and using for bund, including forming and consolidation	C.yd.	0 4 0	324	81
2	Burnt stone jelly concrete in surki mortar	C.ft.	0 4 6	281	79
3	Size stone in surki	C.ft.	0 5 0	749	234
4	Cement concrete slabs including fixing 1 : 2 : 4	C.ft.	1 0 0	57	57
5	Pointing with cement after raking joints, etc.	Sqr.	5 0 0	8·08	40
6	Providing and fixing undressed toe slabs	S.ft.	0 6 0	148	56
7	Do do for pin slabs ..	Each.	2 0 0	5	10
8	New rough stone work including lead, lift and royalty	C.yd.	1 10 0	48½	79

V. V. PATANKAR,
Executive Engineer.